VILLAGE OF TAOS SKI VALLEY Village Council Agenda Item

AGENDA ITEM TITLE: Approval of the Change Order for Contractor Ovivo USA LLC to Change Scope from MBR System to MicorBLOX MBR System

DATE: March 12, 2019

PRESENTED BY: John Avila, Village Administrator

STATUS OF AGENDA ITEM: New Business

CAN THIS ITEM BE RESCHEDULED: Not Recommended

BACKGROUND INFORMATION: This project is underway with engineering and preliminary construction design in last year's building season. The work has been changed in order to use a more appropriate system, so the Order to Change Scope is required to move to develop a microBLOX MBR system instead of a MBR system.

An informal agreement has been reached. (FEI) Allen Plummer Associates prepared the change order paperwork and the change order is attached. It has been signed by OVIVO USA and now requires Village acceptance.

The Change Order is urgent to allow fabrication and delivery in time for construction.

STAFF RECOMMENDATION: Approval of Change Order for OVIVO to produce the microBLOX MBR system components, for the upgraded Wasted Water Treatment Plant construction.


C-941 - CHANGE ORDER

Change Order No. 1

Owner:	Village of Taos Ski Valley	
Contractor:	Ovivo USA LLC.	
Engineer:	Alan Plummer Associates	
Project:	Wastewater Treatment Plant	Expansion
The Contract is mod	dified as follows upon execution	n of this Change Order.
Description:	pe Change from MBR system to	n microBLOX MBR system
	or change from Fibre System to	- Microbiox Fibro System
Attachments:		
	ge Order #1 Technical Proposa	l; Equipment Delivery Date Commitment
CHANGE I	N CONTRACT PRICE	CHANGE IN CONTRACT TIMES [note changes in Milestones if applicable]
Original Contract Pr	rice:	Original Contract Times:
		Substantial Completion:
\$ 1,048,891.78		Ready for Final Payment: calendar days or dates
☐ Increase ☐ De	crease from previously	[Increase] [Decrease] from previously approved
	Orders No to No.	Change Orders No to No:
		Substantial Completion:
\$NA		Ready for Final Payment:
Contract Price prior	to this Change Order:	calendar days Contract Times prior to this Change Order:
	to ano onango oraci.	Substantial Completion:
\$ <u>1,048,891.78</u>		Ready for Final Payment:
Inguage of this Ch	anna Oudau	calendar days or dates
Increase of this Cha	ange Order:	[Increase] [Decrease] of this Change Order:
		Substantial Completion:
\$ <u>2,298,584.22</u>		Ready for Final Payment: calendar days or dates
Contract Price incorporating this Change Order:		Contract Times with all approved Change
Contract Price incor	porauling this Change Order:	Orders: Equipment Delivery: 20 Weeks from
		Submittal Approval
\$ <u>3,347,476.00</u>		Ready for Final Payment: Per Contract Terms calendar days or dates

March 2019

RECOMMENDE By:	D: Patro Bin
	Engineer (Authorized Signature)
Print Name:	Patrick O'Brien
Title:	Principal
Date:	03/07/19
ACCEPTED: By:	
	Owner (Authorized Signature)
Print Name:	
Title:	
Date:	
RECEIVED: By:	O'L
	Contractor (Authorized Signature)
Print Name:	Hiren Trivedi
Title:	Managing Director, Ovivo USA LLC .
Date:	02-07-2019
APPROVED: By:	
	Funding Agency (Authorized Signature)
Print Name:	
Title:	
Date:	






Change Order #1 Technical Proposal Village of Taos Ski Valley, NM Ovivo Proposal #100518-1-AK-R2

PREPARED FOR:

Mark Dahm, P.E. Senior Project Manager FEI Engineers, Inc. 1485 Florida Road, Suite C206 Durango, CO 81301 Phone: (970) 247-0724


> CLIENT **ENGINEER** OVIVO



CREATED: 1/13/2019

VALID UNTIL: 03/13/2019

REPLACEMENT



RETROFIT

REUSE





2404 Rutland Drive, Austin, TX 78758



table of contents ovivo mbr - one system, many solutions

Se	ection 1 – Technical Design	
a.	Commentary on Technical Design	2
b.	Influent Flow Data	3
c.	Influent Effluent Characteristics	3
d.	Membrane System Design	4
e.	Membrane System Design	4
	ection 2 – Scope of Supply	
a.	Equipment Scope Summary	5
b.	Equipment Scope Summary	5
c.	Controls Scope Summary	7
d.	Services Scope Summary	7
e.	Construction Supervision	8
f.	Construction Supervision	9
	ction 3 – Warranty and Support Considerations	
a.	Warranty Summary	10
h	Warranty Management Tools	10

Appendix - Supplementary Information

PIDs

Tie-Point Drawings

PIDs




section 1 technical proposal

1.a Commentary on Technical Design and Performance Requirements

Ovivo's design considerations pay respect to a simplistic flow sheet to capture maximum value in capital, construction, and operational costs. There are diverse techniques in which the design may be approached. A cost effective MBR system design is a balancing act between process flexibility, turndown, energy efficiency, bio-hydraulics and sustainable membrane flux while meeting the design requirements in accordance with the parameters set forth. Ovivo's proposed MBR system design is focused on key points, noted throughout this proposal, which we believe will bring the most value to the project.





The heart of the system is Ovivo's Ceramic Membrane Technology, comprised of hydrophillic Silicon Carbide UF/MF (0.1μ) flat plate which provides unmatched flux rate, repelling negatively charged particlaes including oil. The chemically inert membrane material can operate in extreme enivronments, a pH range



from 1-14 and high sludge concentrations of 4% organic waste or 10% inorganic waste. The plates have a high resestance to oxidents even ozone. The very hydrophillic nature of membranes, allows the membrane zones to be



shut down and drained without the addition of preservative. Membranes are kept clean with an automated backwash system and a regular maintenance clean (MC) which can utilize non-chlorine based chemicals, such as parasitic acidic or ozone.



On the process side, Ovivo AEROSTRIP® diffusers have been the leading technology to reduce operational costs and improve plant performance. Advanced perforation technology and a high strength polyurethane membrane are the secrets to the AEROSTRIP® fine pore diffusers high performance and long service life. Ovivo guarantees clean water transfer efficiencies of 8.5-10%/m (2.6-3.0% ft) 20' side-water depth (SWD) in virtually all applications.





1.b Influent Flow Data

The influent design flows are summarized in the table below.

Parameter	Flow	Minimum Temperature	Event Duration	
Annual Average Flow (AAF)	200,000 GPD ¹	8° C1	9 consecutive months ¹	
Maximum Month Flow (MMF)	310,000 GPD ¹	8° C1	3 consecutive months ¹	
Peak Day Flow (PDF)	440,000 GPD ¹	8° C ¹	2 consecutive weeks ¹	

^{1.} Assumed, to be verified by consulting engineer.

1.c Influent | Effluent Characteristics,

Influent wastewater flows or loads are summarized below. In the event that the influent exceeds the specifications used in engineering this proposal, or the source of influent changes, the ability of the treatment system to produce the designed treated water quality and/or quantity may be impaired. Ovivo will provide guidance to overcome characteristic variations, however, if the Owner chooses to continue to operate the system, they assume the risk or any additional costs associated with biological upset, increased consumable use or membrane damage.

Parameter	Influent		Effluent	Remarks
BOD	664 mg/L		< 9.1 mg/L	
TSS	300 mg/L		< 9.1 mg/L	
TKN	66 mg/L ¹			
NH ₃	45 mg/L ¹		< 2.1 mg/L	
TN	66 mg/L ¹		< 5.2 mg/L	
TP	12 mg/L ¹	Element of the second	< 0.31 mg/L	
FOG				
Fecal Coliform			< 2.2 CFU	
Turbidity			2 NTU ³	
Alkalinity	150 mg/L			
Grit ⁴ Coarse Suspended Solids (CSS) Screen Capture Efficiencies	< 5 mg/L < 200 mg/L ⁵ 90%		Maximum limit in MBR basing Maximum limit in MBR basing	
Maximum Temperature	2	5° C¹	25° C Used for	Flux Design
Elevation	9,:	260 ft		

Notes:

- 1 Assumed, consultant to verify.
- 3 Measured turbidity shall be \leq 2 NTU on 9 of 10 consecutive samples.
- 4 Particles having a specific gravity > 1.6 and unable to pass through a 65-meshc (0.21 mm) screen.
- 5 May be accomplished with a rescreen if headworks is insufficient.



1.d Membrane System Design,

Parameter	Data 1	Data 2	Data 3
Membrane Unit	M11	UF/MF	316SS Housing
	Flat Plate	Silicon Carbide	0.1 μm (avg)
Membrane Plate Properties	1.625 ft ² /plate	Ave TMP 1.0 to 10 psig	Max TMP 5.8 psig
	65 ft ² per module	40 plates / module	5.7 mm spacing
Membrane Module Properties	2.1' w x 2.25' l x .55'h	79 lbs dry weight	99 lbs wet weight
Membrane Diffuser Properties	Coarse Bubble	15 lbs weight	SS316 Housing
Membrane Unit Configuration	715 ft²/unit	11 Modules per unit	SS314 housing
Number of Membrane Trains	4 ¹	-	
Number of Units per Train	6	Single Row	
Total Membrane Surface Area	17,160 ft ²	24 Units (Towers)	
Flux	MMF 18.0	PDF 26.0	

¹ Membrane redundancy: The system can handle AAF continuously and PPF for 24hrs with one membrane zone offline

1.e Biological System Design

Data is preliminary based on current parameters and may be optimized as final design commences.

Parameter	Data 1	Data 2	Data 3
Pre-Anoxic Zone (PAX)	1 Basin (Existing)	14.5' Side Water Depth	24,400 Gallons Total ¹
Pre-Aeration Zone (PA1)	1 Basin (Existing)	14' Side Water Depth	70,700 Gallons Total ¹
Pre-Aeration Zone (PA2A/B)	2 Basin (Existing)	11.17' Side Water Depth	29,500 Gallons Total ¹
Post-Anoxic Zone (AXP)	2 Basins (Supplemental Tanks)	10.5' Side Water Depth	29,000 Gallons Total ¹
Membrane Zone (MBR)	2 Basins (microBLOX)	10' Side Water Depth	20,900 Gallons Total ¹
	MMF 0	.31MGD	
SRT	Plant 29 days		
MLSS	PAX 12,706 mg/L	PA 12,693 mg/L	MBR 14,758 mg/L
AOR	Total 1,454 lbs O₂/d	PA 1,103 lbs O2/day ¹	MBR 351 lbs O2/day ¹
Waste Sludge	6,800 gallons per day	1.4 %	
Process Balance	MicroC 28 gpd	Alkanity 65 gpd	Phos Reduction 28 gpd
	PPF 0.	44MGD	
SRT	Plant 26 days		
MLSS	PAX 16,363 mg/L	PA 16,351 mg/L	MBR 19,025 mg/L
AOR	Total 2027 lbs O₂/d	PA 1547 lbs O2/day ¹	MBR 480 lbs O2/day ¹
Waste Sludge	7,600 gallons per day	1.9 %	- 1
Process Balance	MicroC 39 gpd	Alkanity 100 gpd	Phos Reduction 39 gpd

^{1.} Total all basins



section 2 scope of supply

The following tables represent the scope of supply for the equipment and services provided by Ovivo. Unless specifically and expressly included in this proposal, pricing provided is limited to the goods, services, quantities, materials, and model numbers as shown. See PIDs for specific quantities and location.

2.a Equipment Scope Summary

	Description	Factory Installed or Shipped Loose IBR Tanks 01/02	Manufacturer
	THE RESIDENCE OF THE PROPERTY		
2	microBLOX® MBR Carbon Steel Tanks	Factory Assembled, Installed On-site	Ovivo
24	SiC M11 Ceramic Membranes	Factory Assembled in MBR 01/02	Ovivo Cembrane
24	Permeate Isolation Valves	Factory Assembled in MBR 01/02	Asahi
24	Membrane Diffuser Isolation Valves	Factory Assembled in MBR 01/02	Keystone
1	Fine Bubble Diffusers	Factory Assembled in MBR 01/02	Aerostrip
2	Permeate Pumps 100 GPM	Factory Assembled Lower Porch	Vogelsang
2	TMP – Pressure Transmitters	Factory Assembled Lower Porch	E&H
8	Pump Isolation Valves	Factory Assembled Lower Porch	Asahi
8	Gauges – Suction and Discharge	Factory Assembled Lower Porch	McDaniel
2	Turbidity Meters	Factory Assembled Lower Porch	Hach
2	Flow Meters	Factory Assembled Lower Porch	E&H
4	UV D438	Factory Assembled Lower Porch	Neo-Tech
2	Level Transmitters	Factory Assembled Lower Porch	E&H
4	Auto Valves – On/Off 4"	Factory Assembled Lower Porch	Asahi
4	Blowers – Air Scour K11	Factory Assembled Lower Porch	FPZ
4	Isolation Valves 6"	Factory Assembled Lower Porch	Keystone
2	Airflow Meters	Factory Assembled Lower Porch	Sierra
2	Blowers – Process Diffusers	Factory Assembled Lower Porch	FPZ
2	Isolation Valves 3"	Factory Assembled Lower Porch	Keystone
2	CIP – Hypo Pumps	Shipped Loose	Blue-White
2	Isolation & Check Valves	Shipped Loose	Asahi
2	CIP – Acid Pumps	Shipped Loose	Blue-White
2	Isolation & Check Valves	Shipped Loose	Asahi
2	Level Transmitter – CIP Wet Well	Factory Assembled Wet Well 01/02	Blue Ribbon
1	Lot Pipe, Valves and Electrical	Factory Assembled in Tank and Porches	Ovivo
1	Stair	Shipped Loose, Installed Onsite	Ovivo
2	Walkways	Shipped Loose, Installed Onsite	Ovivo
	PAXI	Process Tanks 01/02	
2	Supplemental tank Carbon Steel	Shipped Loose,	Ovivo
2	Mixer with Rails	Factory Assembled in Process Tanks	Wilo
1	Lot Pipe and Electrical	Factory Assembled in Tank and Porches	Ovivo
	The state of the s	dworks Equipment	
1	2 mm Single Entry Drum Screen	Factory Assembled, Installed Onsite	Ovivo
1	304SS Tank	Factory Assembled in SS Box	Ovivo
1	Flow Meter	Shipped Loose, Installed Onsite	E&H
1	Screw Press, 304SS	Factory Assembled in SS Box	Ovivo

This document is confidential and shall remain the sole property of Ovivo. This document may not be reproduced, discussed or distributed in whole or in part without prior written approval of Ovivo. The data and information provided is furnished on a restricted basis and is not to be used in any way detrimental to the interests of Ovivo.



	PAX	01 Existing Basin			
1	Mixer with Rails	Shipped Loose, Installed Onsite	Wilo		
1	Level Transmitters	Shipped Loose, Installed Onsite	Blue Ribbon		
NE	PA 01/0	02/03 Existing Basins			
3	Transfer Pumps – 1069 GPM	Shipped Loose, Installed Onsite	Wilo		
1	Flow Meter 8"	Shipped Loose, Installed Onsite	E&H		
3	Isolation Valves 8"	Shipped Loose, Installed Onsite	TBD		
3	Check Valves 8"	Shipped Loose, Installed Onsite	TBD		
6	Level Switches	Shipped Loose, Installed Onsite	Conery		
3	LDO Probes	Shipped Loose, Installed Onsite	Hach		
2	Blowers - 881 SCFM	Shipped Loose, Installed Onsite	Aerzen		
1	Airflow Meter 8"	Shipped Loose, Installed Onsite	Sierra		
2	Blower Isolation Valves *"	Shipped Loose, Installed Onsite	Keystone		
1	Fine Bubble Diffusers	Shipped Loose, Installed Onsite	Aerostrip		
3	Mixer with Rails	Shipped Loose, Installed Onsite	Wilo		
3	Level Transmitters	Shipped Loose, Installed Onsite	Blue Ribbon		
		Existing Clarifier Basins			
4	Transfer Pumps – 1069 GPM	Shipped Loose, Installed Onsite	Wilo		
2	Flow Meters 8"	Shipped Loose, Installed Onsite	E&H		
4	Isolation Valves 8"	Shipped Loose, Installed Onsite	TBD		
4	Check Valves 8"	Shipped Loose, Installed Onsite	TBD		
4	Level Switches	Shipped Loose, Installed Onsite	Conery		
2	LDO Probes	Hach			
2	pH Meter	Shipped Loose, Installed Onsite Shipped Loose, Installed Onsite	Hach		
2	Blowers - 441 SCFM	Shipped Loose, Installed Onsite	Aerzen		
2	Airflow Meter 6"	Shipped Loose, Installed Onsite	Sierra		
2	Blower Isolation Valves *"	Shipped Loose, Installed Onsite	Keystone		
1	Fine Bubble Diffusers	Shipped Loose, Installed Onsite	Aerostrip		
2	Mixer with Rails	Shipped Loose, Installed Onsite	Wilo		
2	Level Transmitters	Shipped Loose, Installed Onsite	Blue Ribbor		
-		WAS			
2	Pumps – 100 GPM	Factory Assembled Large Lower Porch	Vogelsang		
2	Auto Valves 2" – Wasting & Rescreening	Factory Assembled Large Lower Porch	Asahi		
1	Flow Meter	Shipped Loose, Installed Onsite	E&H		
2	Check Valves 2"				
4	Isolation Valves 2"	Factory Assembled Large Lower Porch A			
4	Gauges – Suction and Discharge	Factory Assembled Large Lower Porch	McDaniel		
		Dosing Systems			
2	Alum Dosing System	Shipped Loose, Installed Onsite	Blue/White		
2	Carbon Dosing	Shipped Loose, Installed Onsite	Blue/White		
2	pH Addition Mag H	Shipped Loose, Installed Onsite Blue/White			



2.c Controls Scope Summary

QTY	Description	Factory Installed or Shipped Loose	Manufacture			
PLC Panel						
1	PLC/HMI Cabinet, Auto Dialer, Climate Control	Shipped Loose, Installed Onsite	Ovivo			
	Remo	ote IO				
2	Panels	Factory Assembled in Panel	Ovivo			
	HMI/S	SCADA				
1	HMI Panel, HOA, SCADA	Factory Assembled in PLC Panel	Ovivo			
	Motor (Controls				
1	Starter, VFDs as required off board Equipment	Factory Assembled Shipped Loose	Ovivo			
1	Starter, VFDs as required Skid Mounted Equipment	Factory Assembled Shipped Loose	Ovivo			

2.d Services Scope Summary

Ovivo's scope of services is shown below.

Person Days (Total All Trips)	Trips	Provider
t On-site Construct	ion Servi	ces ¹
15	1	Ovivo Technical Services
Support Services ¹		
As Needed	0	Ovivo Technical Services
Management		
1 Year	NA	Ovivo 2-years Subscription
Freight	No. 1	
	4	Ovivo
- T	t On-site Constructi 15 Support Services As Needed Management 1 Year	t On-site Construction Servi 15 1 Support Services As Needed O Management 1 Year NA Freight

Notes:

1. Additional time available at our published labor rates.



2.e Construction Supervision

Ovivo's Project Manager will provide review and supervision of work. Supervision will be completed both remotely and onsite in context of stated man-days included.

The following items would be included in the Supervision of Work carried out by Ovivo.

- Time will be spent making sure the parties involved in the installation of the equipment are well briefed and guided on the correct installation of the equipment.
- An Ovivo representative will provide advice and answer any questions that the contractor may have regarding the installation of Ovivo supplied equipment.
- The Ovivo representative will field questions, give direction on completing the installation, and resolve discrepancies with drawings.
- Ensure the installation work has been carried out correctly and has reached a degree of completion adequate to allow the project to proceed smoothly, without delays.
- The installation of the equipment will be reviewed with the contractor's supervisors/project managers.
- Ovivo will verify installation correctness of interconecting piping.
- Ovivo will verify equipment and instrumentation wiring, conduit and other appurtenances required to
 provide connections as needed between the various field mounted valves and instruments to the
 Local Panel(s) and between any Local Panel(s) and the Master microBLOX™ PLC/MCP Panel.
- Ovivo will witness integrity testing of the basins and piping performed by the contractor or others.
- Working with the contractor, Ovivo's personnel will functionally test Ovivo's system inputs/outputs points to confirm wiring. Remediation of wiring problems is the responsibility of others.
- Upon completion of satisfactory installation, acceptance sheets shall be completed for each subsystem.
- Ovivo will verify that the equipment installation is adequate to allow the plant to be commissioned.
- Upon completion of onsite visit, Ovivo's representative will develop a Contractor's Punch list. The
 punch list will identify items that are incomplete or outstanding. It is Ovivo's expectation that all
 punch list items be resolved prior to the next visit. Failure to properly address punch list items
 proactively can result in unplanned delays.





2.f Scope by Others

Time will be spent making sure the parties involved in the installation of the equipment are well briefed. The following items are for the supply and responsibility of the owners representatives, consultants, construction contractor or others:

- Overall plant design;
- Review of equipment drawings and specifications;
- Unloading of delivered equipment at the FOB site including receiving, sign-off and safe storage of equipment at site until ready for installation;
- Construction Contractor to provide suitable warehousing for storage of the materials;
- Equipment installation including, but not limited to the following;
 - Installation of any other loose-shipped Ovivo supplied equipment;
 - Flushing of contractor supplied interconnecting piping;
 - Verification of removal of all residual debris from construction. Debris found within the tank can potentially void membrane warranties or require immediate replacement of damaged cassettes;
 - Providing assistance where necessary to electrical trades in the accomplishment of functions requiring mechanical tradesmen (including pipe fitters and any other trade within the scope of this contract);
 - Touch up finish paint surfaces on equipment as required at the completion of the project;
- Facilities for the disposal of raw water screening and pretreatment of feed water;
- Civil and structural works, provision of main plant structures, tank construction, buildings, equipment foundation pads etc. including, but not be limited to the following:
- Construction of foundation pads for the major process equipment;
- Installation of equipment access platforms, walkways, stairs etc.
- Equipment anchor bolts and tank anchors other than factory installed equipment;
- Design, supply, installation and testing of process and utilities piping, pipe supports, hangers, valves etc. supplied by the general contractor;
- Installation of all power and instrumentation interconnecting wiring, optical fibers, conduit and appurtenances from the control panels, MCC's etc. to field mounted instruments, motors, valves/valve actuators and any other equipment supplied by Others or Ovivo including, but not limited to;
 - Electrical wiring interconnections (including wiring, conduit and any other appurtenances required to provide power connections as needed) from the electrical power source to the PLC /Motor Control Panel;
 - Instrumentation wiring, conduit and other appurtenances required to provide connections as needed between the various field mounted valves and instruments to the Local Panel(s) and between any Local Panel(s) and the Master microBLOX™ PLC/MCP Panel;
 - All junction boxes, disconnect switches and local operator controls required by the contract drawings and specifications, site standards and local codes and regulations;
- Any raw materials, and utilities during equipment start-up and operation including seed sludge and a supply of raw water feed that meets all design parameters for the successful commissioning of the membrane equipment;
- Chemical totes and any chemicals for operation;
- Laboratory services, operating and maintenance personnel required during equipment checkout, start-up and operation;



 Collection and disposal offsite as applicable for spent water, including disposal of membrane rinse and flush waters.

section 3 warranty and support considerations

3.a Warranties

Warranties presented in this proposal are:

Warranty	Description ¹	Duration Yrs	Туре
	Membrane		
Workmanship	Workmanship and Defects	5	Full
Performance ²	Membrane Throughput and Integrity	5	Full
	Equipment		
Ancillary	Workmanship	1	Full
	MBR System		
Process ²	System Process Performance	1	

Notes:

3.b Warranty Management Tools

WaterExpert™ is included for the first year of operation. WaterExpert™ is a platform provided to help better maintain and operate the equipment and harness the power of cloud to provide real time data insights into the equipment. Included in the WaterExpert™ base plan are data trending charts, alerts, maintenance calendars, digital documentation of Ovivo's scope of supply, drawings, IOM manuals and generic videos of basic process, operation and maintenance your MBR equipment.

At Commissioning, Ovivo start-up personnel will provide onsite training of the system as well as the use of the WaterExpert™ digital operation tools.



These tools can be accessed from any smart phone, tablet or computer. A brief video demonstrating WaterExpert™ capabilities is available at the following youtube link:

This document is confidential and shall remain the sole property of Ovivo. This document may not be reproduced, discussed or distributed in whole or in part without prior written approval of Ovivo. The data and information provided is furnished on a restricted basis and is not to be used in any way detrimental to the interests of Ovivo.

See warranty statements and specifications for full description.

^{2.} Must have WaterExpert maintained.



technical proposal appendix supplementary information

PIDs
Tie-Point Drawings
BioWin Summary

VILLAGE OF TAOS SKI VALLEY Village Council Agenda Item

AGENDA ITEM TITLE: Consideration to Approve Entering the Joint Powers Agreement for the Taos Regional Landfill

DATE: March 12, 2019

PRESENTED BY: John Avila, Village Administrator

STATUS OF AGENDA ITEM: New Business

CAN THIS ITEM BE RESCHEDULED: Not Recommended

BACKGROUND INFORMATION:

The members of the Taos Regional Landfill have been working for several years on the framework for forming a JPA. Under the JPA a Board of Directors is formed by one representative of each of the participating Parties. The Governing Body of each Party to the JPA shall appoint a representative (Director) to the JPA Board.

The Board representative must be a member of the governing body or the Manager or Administrator. The Council may also appoint an Alternative Director to serve when the Representative Director is unable.

The JPA will be an enterprise fund and public entity self-funding from Landfill Revenues but the JPA will also be able to apply for public grant funding and issue revenue bonds.

STAFF RECOMMENDATION: Staff recommends approval to join the Taos Regional Landfill Joint Powers Agreement and to appoint Mayor Brownell as the Village of Taos Ski Valley Representative Director to the Board and Administrator Avila as the Alternative Director.

AMENDED AND RESTATED JOINT POWERS AGREEMENT FOR THE TAOS REGIONAL LANDFILL

This Joint Powers Agreement for the Taos Regional Landfill (hereinafter referred to as "JPA" or "the JPA") is entered into pursuant to the Joint Powers Agreements Act, NMSA 1978 §§ 11-1-1 through 11-1-7 (hereinafter referred to as "the JPA Act"), by and between Taos County, a political subdivision of the State of New Mexico (hereinafter referred to as "the County"), the Town of Taos, New Mexico, a municipal corporation organized and existing under the Laws of the State of New Mexico (hereinafter referred to as "the Town"), the Village of Questa, a municipal corporation organized and existing under the Laws of the State of New Mexico (hereinafter referred to as "Questa"), the Town of Red River, a municipal corporation organized and existing under the Laws of the State of New Mexico (hereinafter referred to as "Red River"), the Village of Taos Ski Valley, a municipal corporation organized and existing under the Laws of the State of New Mexico (hereinafter referred to as "Taos Ski Valley"), and the Village of Eagle Nest, a municipal corporation organized and existing under the Laws of the State of New Mexico (hereinafter referred to as "Eagle Nest")(collectively referred to herein as "the Parties"), effective as of the date of last signature of the Parties hereto and the date of approval of this JPA by the Department of Finance and Administration.

RECITALS

- A. Pursuant to NMSA 1978, §§ 3-48-1 through 3-48-7, the Town has statutory authority to dispose of solid waste and to operate a solid waste facility;
- B. Pursuant to NMSA 1978, §§ 4-56-1 through 4-56-3, the County has the statutory authority to dispose of solid waste and to operate a solid waste facility;